

#



भाकृअनुप - प्याज एवं लहसुन अनुसंधान निदेशालय

राजगुरुनगर, पुणे- 410505 (महाराष्ट्र)

ICAR - Directorate of Onion and Garlic Research

Rajgurunagar, Pune-410505 (Maharashtra)

Phone No.(02135) 222026, Fax: (02135) 224056, Email: director@dogr.res.in



मिसिल संख्या:- 16-11/Work/14-15

दिनांक:- 06/01/2015

सेवा में/To

विषय: डी.ओ.जी.आर .के कालूस प्रक्षेत्र पर क्यूरिंग शेड बनवाने के कार्य हेतु सीमित निविदा) कोटेशन (आमंत्रित करने के बारे में ।


Sub. : Limited tender (Calling quotation) for Carry out Construction of curing shed at DOGR, Kalus

महोदय / Sir,

उपरोक्त विषय के संदर्भ में इस निदेशालय के कालूस फार्म पर क्यूरिंग शेड बनवाने के कार्य हेतु सरकारी लाइसेंस धारक प्रतिष्ठित ठेकेदार फर्मों /ठेकेदारों से सीमित निविदा) कोटेशन (आमंत्रित की जाती हैं । आप इस संबंध अपने मुहरबंद प्रस्ताव सभी नियमों और शर्तों के साथ लिफाफे के ऊपर “ डी.ओ.जी.आर .के कालूस प्रक्षेत्र पर क्यूरिंग शेड बनवाने के कार्य हेतु निविदा) कोटेशन(” लिखकर निदेशक, प्याज एवं लहसुन अनुसंधान निदेशालय , राजगुरुनगर, पुणे को **10/02/2015** तक प्रस्तुत कर सकते हैं । आवश्यक विवरण नीचे दिया गया है तथा अधिक जानकारी हेतु आप निदेशालय की वेबसाईट www.dogr.res.in भी देख सकते हैं ।

With reference to above subject, limited tender (Quotations) are invited from Government licence holder reputed contractor for 'Carry out construction of curing shed at DOGR- Kalus. In this connection you may submit your sealed proposal along with all terms and conditions superscribed as “**Quotation for Construction of curing shed at DOGR- Kalus** ” to the Director, DOGR, Rajgurunagar, Pune upto **10/02/2015**. Important specifications are given below and you may also visit at DOGR's website www.dogr.res.in for details.

Sr. No.	Description	Qty.	Unit	Rate	Amount
	As per Annexure- I				


Administrative Officer


Copy to:

1. Sh. Vishwanath Yelmalle, Scientist and I/c. RFS, DOGR, Kalus Centre.
2. Dr. A.Thangasamy, Chairman -Works Committee, DOGR, Rajgurnagar, Pune.
3. I/C Estate, DOGR, Rajgurunagar, Pune.
4. AFAO, DOGR, Rajgurunagar, Pune.
5. PS-to-Director, DOGR, Rajgurunagar, for information please.
6. Guard file

P.T.O. for Term & conditions

Term & conditions:-


1. Company profile along with PAN/TAN, Bank Account detail should be provided with the tender document.
2. The above work should be commenced immediately after finalization of the proposal and completed as per DOGR's schedule; otherwise this Directorate reserves right to impose the penalty of 2% per week on the amount of purchase orders.
3. Interested firms should apply with their detailed Company profile along with PAN/TAN and Bank Account detail.
4. The quoted price should be F.O.R. DOGR, Rajgurunagar only.
5. Quoted price should be inclusive of all taxes, material and transportation charges, no other charges shall be paid extra.
6. All rates should be on actual area basis only.
7. An amount of Rs. 10,000/- (Ten thousand) only should be deposited in the form of Bank's demand draft favoring "**ICAR-UNIT DOGR**" towards EMD (refundable) along with tender document in respect of above tender.
8. Selected bidder should have to deposit Performance security amount equivalent to 10% of total estimate/final value of purchase order, before commencement of work.
9. Quoted rates should remain valid upto 90 days (minimum) from the date of opening of tender.
10. All applicable taxes and charges, term & conditions, discount (if any), commencement schedule/period should be clearly mentioned in your proposal.
11. T.D.S. @ 2% will be deducted on the amount from the final bill of the selector contractor.
12. Payment will be made only after completion of work based on actual measurement area, our requirement and necessary certification of our consultant engineer against bill.
13. Directorate reserves the right for cancellation without sending any information.
14. All right to Rajgurunagar jurisdiction.
15. Receipt of this letter may please be acknowledged.


Administrative Officer

S. NO.	Description	Qty.	Unit	Rate	Amount
1.	Excavation for foundation earth, soils of all types. Sand and gravel and soft murum including removing the excavated material upto a distance of 50 meters beyond the building area and stacking and spreading as directed, dewatering preparing the bed for the founding and necessary back filling, ramming watering including shoring & shuttering etc. Complete.	63.59	Cum		
2.	Providing and laying casting situ cement concrete 1:4:8 of trap/granite quartzite/geniss metal for foundation and bedding including bailing water, formwork compacting, curing etc. Complete. Spec No. 3 BDA IC Page No. 13	1.2	Cum		
3.	Providing and laying cast in situ cement concrete 1:2:4 of trap/ granite/gneiss metal for R.C.C. work in foundations like raft, grilles, strips, foundations and footings of R.C.C. columns and steel stanchions etc including bailing out water, formwork, compaction, curing and roughening the surface if special finish is to be provided. Spec. No. 6BDF2b page No. 20	4.37	Cum		
4.	Providing & casting in situ cement concrete 1:2:4 for trap/granite/quartzite/gneiss metal coloumns as per detailed drawing & designs, or as directed included catering directed included, centering, special finish is to be provided & curing complete. Spec. No. 10BDF 4 b page No. 21	0.41	Cum		
5.	Providing dry trap/granite/quartzite/Gneiss rubble stones soiling 15cm to 20cm Th. Cluding hand packing and in compacting complete. Spec. No. Rd19 page no. 197	2.76	Cum		
6.	Providing second class burnt brick masonry In cement mortar 1:4 including scaffolding, Racking joint pointing in C. M. 1:4 for Parapet & steps. 3BDG 2A	5.61	Cum		
7.	Coping Providing and laying casting situ cement concrete 1:4	0.94	Cum		
8.	Filling in plinth & floors with contractor's sand or Murum in 23cm, layers including watering & compaction complete. Spec. No. 14BDA 11 page no. 8	47.63	Cum		
9.	Providing and fixing in position HYSD bar reinforcement of various dia. For RCC pile slab, footings, column, beam, as per detailed drg and schedules including cutting bending hooking the bars binding with wires and supporting as per required complete.	0.70	MT		

--Continue to page No. 2

10.	Providing structural steel work in trusses, other similar trussed purlins, etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting erecting fixing in position, making welded/bolted/riveted connections and one coat of anticorrosive paint and over it 2 coat of oil painting complete	2.50	MT		
11.	Providing and fixing asbestos cement sheet of 0.63 mm thick for roofing without wind tiles including fastening with galvanizing/iron screw/bolts and lead/bitumen washers as per drawing complete.	125.09	Sqm.		
12.	Providing sand faced plaster externally in to coat to concrete, brick masonry surfaces in all positions with base coat of 12 to 15mm thick in CM. 1:4 and rough cast treatment 12mm thick in proportion 1:1 ½ :3 including scaffolding and fourteen days curing complete Spec. No. BL8 page no. 370	52.68	Sqm		
13.	Providing and fixing bolts including necessary socket union nuts .etc. complete.	96.00	Nos		
14.	Providing & applying waterproof cement paint of approved manufacturer and approved colour etc. Complete.	52.68	Sqm		
15.	Providing and fixing water gutter completed.	30.00	Rmt		
16.	Providing and laying 1:2:4 concrete for loading unloading area completed	6.90	Cum		


Administrative Officer